

<b>Linear joint, horizontally in block work</b>		10.15
<b>Fire Resistance Test In Accordance With EN 1366-4 / block work wall 100mm</b>		
Linear joint, horizontally	with Firetect Flex strip 56 x 50 mm (wxd) on exposed side	<b>EI 60 minutes</b>
joint 50 mm		

